Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work: Improvements to roads and drain 18th main, 19th main, 20th main road and Surrounding Area of Judicial layout in ward no. 04, Yelahanka Uphanagara

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Civil Work								
1	**Removing and refixing stone slabs** of drains and pointing in CM (1:3) (P.No-27,I No-5.33,KPWD SR 2018-19)								
	Basic rate	105.00							
	Area Weightage 6%	6.30							
	Total	**111.30**							
	For Drain Desilt	**Sqm**							
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	1.65		264.00		
	18th main		2	252.00	1.65		831.60		
	26th cross		2	185.00	1.65		610.50		
	18th cross		2	36.00	1.65		118.80		
	13th main		2	160.00	1.65		528.00		
	Cross Road A		2	190.00	1.65		627.00		
	Cross Road B		2	240.00	1.65		792.00		
	Cross Road C		2	120.00	1.65		396.00		
							4167.90		
	Consider 20%						833.58		
							3334.32	**111.30**	**371109.82**
2	KSRRB 300-1. **Earthwork excavation by manual means** for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(I No-19.1, P No-143), 10km lead								
	Basic rate	130.00							
	Area Weightage 6%	7.80							
	Loading and Unloding &	82.60							
	Total	**220.40**							
		Cum							
	For Drain Desilt								
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	0.45	0.40	28.80		
	18th main		2	252.00	0.45	0.40	90.72		
	26th cross		2	185.00	0.45	0.40	66.60		
	18th cross		2	36.00	0.45	0.40	12.96		
	13th main		2	160.00	0.45	0.40	57.60		
	Cross Road A		2	190.00	0.45	0.40	68.40		
	Cross Road B		2	240.00	0.45	0.40	86.40		
	Cross Road C		2	120.00	0.45	0.40	43.20		
	Culvert		2	6.50	1.50	1.10	21.45		
	RCC Drain								
	Cross Road 1		2	90.00	1.10	1.10	217.80		
	Cross Road 2		2	80.00	1.10	1.10	193.60		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
							887.53	220.40	195611.61
3	KSRRB M2100-10. Providing and laying **Plain cement concrete of mix 1:3:6** with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, In foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	Basic rate	5115.00							
	Area Weightage 6%	306.90							
	Total	**5421.90**							
		Cum							
	Ward 4								
	Judicial Layout								
	RCC Drain								
	Cross Road 1		2	90.00	1.10	0.15	29.70		
	Cross Road 2		2	80.00	1.10	0.15	26.40		
	Culvert		2	6.50	1.50	0.15	2.93		
							59.03	5421.90	320027.65
4	Providing and laying plain/reinforced cement concrete for side drains using **M20 nominal mix concrete with OPC at 300 kgs.** With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19)								
	Basic rate	6670.00							
	Area Weightage 6%	400.20							
	Total	**7070.20**							
		Cum							
	Ward 4								
	Judicial Layout								
	RCC Drain								
	Raft								
	Cross Road 1		2	90.00	0.90	0.15	24.30		
	Cross Road 2		2	80.00	0.90	0.15	21.60		
	Wall								
	Cross Road 1		4	90.00	0.15	0.60	32.40		
	Cross Road 2		4	80.00	0.15	0.60	28.80		
	Culvert		2	6.50	1.20	0.20	3.12		
	Culvert		4	6.50	0.23	0.60	3.59		
							113.81	7070.20	804645.32
5	KSRRB - M2300-14: Providing **TMT steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)								
	Basic rate	69804.00							
	Area Weightage 6%	4188.24							

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Total	73992.24							
		Tn							
	Ward 4								
	Judicial Layout								
	RCC Drain								
	For Drain 60kg/cum			113.81	0.06		6.83		
	For Culvert 90kg/cum			6.71	0.09		0.60		
							7.43	73992.24	549925.13
6	Providing and Fixing **pre cast covering Slab 100mm thick** made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)								
	Data rate	2337.00							
		Sqm							
	Ward 4								
	Judicial Layout								
	RCC Drain								
	Cross Road 1		2	90.00	0.90		162.00		
	Cross Road 2		2	80.00	0.90		144.00		
							306.00	2337.00	715122.00
7	Providing and fixing RCC **precast cover slab of 250mm thick** for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
	Data rate	5418.00							
		Sqm							
	Ward 4								
	Judicial Layout								
	Culvert		2	6.50	1.20		15.60		
							15.60	5418.00	84,520.80
8	**Providing granite slabs** of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 7.5 cms thick (I No-5.31.1,P No-27,KPWD SR 2018-19)								
	Basic rate	700.00							
	Area Weightage 6%	42.00							
	Total	742.00							
		Sqm							
	Missing slabs from item no. 1, 25%						1041.98		
							1041.98	742.00	773145.45
9	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 10km lead= (I No-19.14,P No-143,KPWD SR 2018-19), 10kms lead								
	Basic rate	41.00							
	Area Weightage 6%	2.46							
	Loading and Unloding & Lead	25.60							

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Total	69.06							
		Cum							
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	1.20	0.20	38.40		
	18th main		2	252.00	1.10	0.20	110.88		
	26th cross		2	185.00	1.00	0.20	74.00		
	18th cross		2	36.00	1.20	0.20	17.28		
	13th main		2	160.00	1.00	0.20	64.00		
	Cross Road A		2	190.00	1.00	0.20	76.00		
	Cross Road B		2	240.00	1.00	0.20	96.00		
	Cross Road C		2	120.00	1.00	0.20	48.00		
							524.56	**69.06**	**36,226.11**
10	**Construction of granular sub-base Grading-V** as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	Basic rate	1882.00							
	Area Weightage 6%	112.92							
	Total	**1994.92**							
		Cum							
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	1.20	0.15	28.80		
	18th main		2	252.00	1.10	0.15	83.16		
	26th cross		2	185.00	1.00	0.15	55.50		
	18th cross		2	36.00	1.20	0.15	12.96		
	13th main		2	160.00	1.00	0.15	48.00		
	Cross Road A		2	190.00	1.00	0.15	57.00		
	Cross Road B		2	240.00	1.00	0.15	72.00		
	Cross Road C		2	120.00	1.00	0.15	36.00		
							393.42	**1994.92**	**784841.43**
11	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Basic rate	1888.00							
	Area Weightage 6%	113.28							
	Total	**2001.28**							
		Cum							
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	1.20	0.23	44.16		
	18th main		2	252.00	1.10	0.23	127.51		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	26th cross		2	185.00	1.00	0.23	85.10		
	18th cross		2	36.00	1.20	0.23	19.87		
	13th main		2	160.00	1.00	0.23	73.60		
	Cross Road A		2	190.00	1.00	0.23	87.40		
	Cross Road B		2	240.00	1.00	0.23	110.40		
	Cross Road C		2	120.00	1.00	0.23	55.20		
							603.24	**2001.28**	**1207260.15**
12	KSRRB M500-6. Providing and **applying primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6), issue rate dated 20-05-2020								
	Basic rate	25.00							
	Area Weightage 6%	1.50							
	Total	**26.50**							
		Sqm							
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	1.20		192.00		
	18th main		2	252.00	1.10		554.40		
	26th cross		2	185.00	1.00		370.00		
	18th cross		2	36.00	1.20		86.40		
	13th main		2	160.00	1.00		320.00		
	Cross Road A		2	190.00	1.00		380.00		
	Cross Road B		2	240.00	1.00		480.00		
	Cross Road C		2	120.00	1.00		240.00		
							2622.80	**26.50**	**69,504.20**
13	KSRRB 500-7. Providing and applying **tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7) issue rate dated 20-05-2020								
	Basic rate	12.00							
	Area Weightage 6%	0.72							
	Total	**12.72**							
		Sqm							
	Ward 4								
	Judicial Layout								
	24th cross		1	80.00	5.20		416.00		
	18th main		1	252.00	6.50		1638.00		
	26th cross		1	185.00	5.20		962.00		
	18th cross		1	36.00	5.30		190.80		
	13th main		1	160.00	5.20		832.00		
	Cross Road A		1	190.00	5.50		1045.00		
	Cross Road B		1	240.00	6.00		1440.00		
	Cross Road C		1	120.00	5.50		660.00		
							7183.80	**12.72**	**91,377.94**

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
14	KSRRB M500-17. Providing and laying **dense graded bituminous macadam** using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revisionusing 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6), issue rate dated 20-05-2020								
	Basic rate	5403.00							
	Area Weightage 6%	324.18							
	Total	**5727.18**							
		Cum							
	Ward 4								
	Judicial Layout								
	24th cross		2	80.00	1.20	0.05	9.60		
	18th main		2	252.00	1.10	0.05	27.72		
	26th cross		2	185.00	1.00	0.05	18.50		
	18th cross		2	36.00	1.20	0.05	4.32		
	13th main		2	160.00	1.00	0.05	16.00		
	Cross Road A		2	190.00	1.00	0.05	19.00		
	Cross Road B		2	240.00	1.00	0.05	24.00		
	Cross Road C		2	120.00	1.00	0.05	12.00		
							131.14	**5727.18**	**751062.39**
15	Providing and laying **bituminous concrete 40mm thick** with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015. using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminus binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic)(P.No-171,I No-21.78.12), issue rate dated 20-05-2020								
	Basic rate	6379.00							
	Area Weightage 6%	382.74							
	Total	**6761.74**							
		Cum							
	Ward 4								
	Judicial Layout								
	24th cross		1	80.00	5.20	0.04	16.64		
	18th main		1	252.00	6.50	0.04	65.52		
	26th cross		1	185.00	5.20	0.04	38.48		
	18th cross		1	36.00	5.30	0.04	7.63		
	13th main		1	160.00	5.20	0.04	33.28		
	Cross Road A		1	190.00	5.50	0.04	41.80		
	Cross Road B		1	240.00	6.00	0.04	57.60		
	Cross Road C		1	120.00	5.50	0.04	26.40		
							287.35	**6761.74**	**1942999.51**

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
16	KSRRB M800-13.**Road Marking** with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Basic rate	429.00							
	Area Weightage 6%	25.74							
	Total	**454.74**							
		Sqm							
	Ward 4								
	Judicial Layout								
	24th cross		2.5	80.00	0.10		20.00		
	18th main		2.5	252.00	0.10		63.00		
	26th cross		2.5	185.00	0.10		46.25		
	18th cross		2.5	36.00	0.10		9.00		
	13th main		2.5	160.00	0.10		40.00		
	Cross Road A		2.5	190.00	0.10		47.50		
	Cross Road B		2.5	240.00	0.10		60.00		
	Cross Road C		2.5	120.00	0.10		30.00		
							315.75	**454.74**	**143584.16**
								Total Construction Cost	**8840963.65**
								Towards GST 12%	**1060915.64**
								PMC Charges 1%	**98,000.00**
								Sub Total	**9999879.29**
								Miscellaneous & Rounding Off	**120.71**
								Total	**10000000.00**

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2018-2019, issue rates dated 03-01-2020 and Data Rates

Assistant Engineer
Ward 04
BBMP Bangalore

Asst. Executive Engineer
Yelahanka New Town Sub Division
BBMP Bangalore

Executive Engineer
Yelahanka Division
BBMP Bangalore

Administrative Sanction for Rs. ....100.00 lakhs
.....
.....
is accorded under head ..14th Finance
Commission Works P.3296
.....
Registered as CE No. .....13..... Subject
to conditions contained in enclosed memo
No. B.B.H.P/E.E/YNK-D.1&S/13/2020-21
29/7/2020

Executive Engineer

Technical Sanction
Accorded For RSIW's Wacherly
Head of A/C P.3296 29.07.2020
CER NO : 51 Dt:...

MTA

CE (YNK)

Judicial layout

Sangolli Rayanna Park
ಸಂಗೊಳ್ಳಿ ರಾಯಣ್ಣ
Temporarily close

22nd Cross rd

25th Main Rd

28th Cross Rd

Judicial Layout Letter Box

Fairly Dense Mixed Jungle
ಫೇರ್ಲಿ ದೆನ್ಸ್ ಮಿಕ್ಸ್ಡ್ ಜಂಗಲ್
Temporarily closed

OYO 71316
Fna Hospitality

21st Main rd

20th Main rd

19th Main rd

14th Main rd

27th cross rd

26th cross rd

25th cross rd

24th cross rd
L-80m

23rd cross rd

18th Main rd
L-262m

17th Main rd

16th Main rd

15th Main rd

26th cross rd
L-185m

25th cross rd

24th cross rd

23rd cross rd

22nd cross rd

Maple Bear Canadian Pre-school

Deccan Shelt

Shashi Pro

25th A Cross Rd

Food Grains

Maruthi
Allal
Tempora

DIA Capital

13th Main rd
L-160m

18th cross rd
L-36m

Na desvara
Pro on Stores

SLV

15th Cross Rd

GKVK Exhibition Ground
Temporarily closed

Google

ASPHALT ROAD

CLIENT:	CONSULTANT:-				
BRUHAT BANGALORE MAHANAGARA PALIKE	Silicon Consulting Engineers #S1317, 4th CROSS BEL 2nd STAGE BHARATH NAGAR BANGALORE 560 091 E-mail siliconcivilengineers@gmail.com	Assitante Engineer	Assitante Executive Engineer	Executive Engineer	Improvements to roads and drain 18th main, 19th main, 20th main road and Surrounding Area of Judicial layout in ward no. 04, Yelahanka Uphanagara Dwg no: Date Revi: R0